

26-0024: UTSW CUH 4.219 Microbiology Lab
6201 Harry Hines Boulevard, Dallas, TX 75235, United States of America

Source Building Group

651 East Debbie Lane, BLDG 200, Mansfield, TX 76063, United States of America

Colton Bennett | Estimator / Quantity Surveyor | +1 210-383-9481 | cbennett@sourcebuild.net



Line Items

Description	Quantity	Unit Cost	Total Cost
Bid Form (8/28/26):			
* Demolition			\$
Base Bid			\$0

Alternates

OWNER BID ALTERNATES:

* None at this time.

\$

Scope Alternates:

* 4" Dia. Coring

\$

* Roof Demolition

\$

* Electrical Demolition

\$

* Mechanical Demolition

\$

* Plumbing Demolition

\$

* Technology Demolition

\$

Inclusions

Mark "yes" to all yes/no questions »

SPECIFICATION(S) ACKNOWLEDGEMENT:

* 02 41 00 - Demolition

☐ Yes ☐ No**SCOPE OF WORK:****Building Interior Demolition:**

* Demolition per Demo Plan(s): SD200, SD250,

☐ Yes ☐ No

* REMOVE EXISTING INTERIOR WINDOW AND FRAME (AD-11 - A-104).

☐ Yes ☐ No

* Remove & salvage existing Laboratory Casework

☐ Yes ☐ No

* Remove existing millwork/casework

☐ Yes ☐ No

* Remove Flooring

☐ Yes ☐ No

* Remove partition walls

☐ Yes ☐ No

* Remove ceilings

☐ Yes ☐ No

* Remove existing wall protection

☐ Yes ☐ No

* Remove & salvage existing signage

☐ Yes ☐ No**General:**

* Protection of Existing Finishes and Conditions

☐ Yes ☐ No

26-0024: UTSW CUH 4.219 Microbiology Lab

6201 Harry Hines Boulevard, Dallas, TX 75235, United States of America

* Remove offsite all debris ☐ Yes ☐ No

* Daily Cleanup before end of every shift. ☐ Yes ☐ No

: _____

PROJECT SPECIFIC SCOPE | NOTES:

* EXISTING LOUVER REMOVAL EXTENTS (SD200) ☐ Yes ☐ No

: _____

Q&A Project Specific Items as of 8/27/26:**Q100. Existing Slab Rebar:**

* Q: Please specify whether the existing concrete slab is Post-Tension or conventional rebar (Asked 4/15/2026 at 3:18 PM CDT). ☐ Yes ☐ No

A: Conventional mild reinforced slab and beam system (Answered 8/6/2026 at 8:54 PM CDT by Marcus Howard).

Q103. 3" Overcut at Cores:

* Q: Plan Note 4 on 2/S200 implies 3" overcut at cores to achieve the specified 1-1/2" minimum bar cover at all reinforcement. Please confirm this is required (Asked 4/15/2026 at 3:17 PM CDT). ☐ Yes ☐ No

A: No overcut required. This note is provided to indicate core minimum clearances from existing framing and existing reinforcement (Answered 8/6/2026 at 8:55 PM CDT by Marcus Howard).

: _____

Scope of for Alternate(s) NOT APART OF BASE BID:**4" Dia Coring (Per Partial Plans (S200)):**

* NO NEW CORES ARE PERMITTED THROUGH EXISTING CONCRETE BEAMS OR COLUMNS. IF REQUIRED, CORES SHOULD ONLY BE DRILLED THROUGH THE EXISTING SLAB (S200) ☐ Yes ☐ No

* NEW 4" MAX DIAMETER CORE THROUGH EXISTING BEAM PERMITTED AT THIS LOCATION ONLY AFTER REBAR SCANS HAVE BEEN PROVIDED FOR EOR REVIEW ON ALL 4 SIDES OF THE BEAM IN THIS LOCATION (S200). ☐ Yes ☐ No

* ALL SLAB REINFORCEMENT SHALL BE LOCATED BY NON-DESTRUCTIVE METHODS PRIOR TO CORING AND END PLATE/BASE PLATE FABRICATION. GROUND PENETRATING RADAR (GPR) IS ONE ACCEPTABLE METHOD FOR LOCATING EXISTING SLAB REINFORCEMENT. ALL CARE SHOULD BE TAKEN NOT TO DAMAGE OR CUT EXISTING SLAB REINFORCEMENT INCLUDING RELOACTING THE CORE TO MISS EXISTING REINFORCEMENT (S200). ☐ Yes ☐ No

Roof Demolition (Per Roof Demolition Plan (A-105)):

* REMOVE MECHANICAL EQUIPMENT ROOF CURBS, FLASHING, AND SUPPORT MATERIAL. PATCH AND REPAIR ROOF (AD-10 - A-105). ☐ Yes ☐ No

* TEMPORARILY COVER/PROTECT OPENINGS UNTIL PROPOSED MECHANICAL EQUIPMENT IS INSTALLED (AD-15 - A-105). ☐ Yes ☐ No

* SALVAGE AND REUSE LOUVER WALL STRUCTURAL STEEL AND ITS ASSOCIATED FLASHING. PATCH AND REPAIR ROOF, AND REFER TO STRUCTURAL FOR ADDITIONAL INFORMATION (AD-17 - A-105). ☐ Yes ☐ No

* REMOVE EXISTING ROOF WALKING PADS AS REQUIRED TO MODIFY AND EXTENT LOUVERED SCREEN WALL (AD-45 - A-105). ☐ Yes ☐ No

* SALVAGE AND RE-USE EXISTING ROOFTOP ANCHOR/DAVIT. PATCH AND REPAIR ROOFING TO MAINTAIN WATER-PROOFING. PATCH AND REPAIR ROOF STRUCTURE (AD-47 - A-105). ☐ Yes ☐ No

* PROVIDE ROOF SLAB OPENINGS FOR MECHANICAL DUCT ROUTING AND EQUIPMENT. TIE INTO EXISTING ROOF SYSTEM AT PENETRATIONS. PROVIDE FIRESTOPPING AT ALL ROOF PENETRATIONS (RF-01 - A-105). ☐ Yes ☐ No

Electrical Demolition (Per Electrical Demolition Plans (E-000, ED-110, ED-111, ED-112)):

* DISCONNECT AND REMOVE EXISTING VFDS SERVING FANS SHOWN TO BE DEMOLISHED ON SHEET ED-113. RETURN VFDS TO OWNER. REMOVE ALL CONDUIT AND CONDUCTORS FROM VFD BACK TO SOURCE AND LABEL AS SPARE BREAKERS IN PANEL SCHEDULE. LOCATION SHOWN IS APPROXIMATE, FIELD VERIFY EXACT LOCATION PRIOR TO SUBMITTING BID. REFER TO MECHANICAL DRAWINGS FOR ADDITIONAL DETAILS (1 - ED-110). ☐ Yes ☐ No

26-0024: UTSW CUH 4.219 Microbiology Lab

6201 Harry Hines Boulevard, Dallas, TX 75235, United States of America

* REMOVE LIGHTING, CONDUIT, WIRING, JUNCTION BOXES AND ASSOCIATED MATERIALS TO SOURCE. DISCARD ALL MATERIALS. LABEL BREAKERS SERVICING SPACES AS "SPARE". VERIFY NO OTHER DEVICES REMAINING IN SERVICE ARE CONNECTED TO REMOVED CIRCUITS. IF SO, MAINTAIN CIRCUITS (1 - ED-111). ☐ Yes ☐ No

* REMOVE FIRE ALARM EQUIPMENT, CONDUIT, WIRING, JUNCTION BOXES AND ASSOCIATED MATERIALS TO SOURCE. DISCARD ALL MATERIALS. VERIFY NO OTHER DEVICES REMAINING IN SERVICE ARE CONNECTED TO REMOVED CIRCUITS. IF SO, MAINTAIN CIRCUITS (2 - ED-111). ☐ Yes ☐ No

* REMOVE RECEPTACLES, CONDUIT, WIRING, JUNCTION BOXES AND ASSOCIATED MATERIALS TO SOURCE. DISCARD ALL MATERIALS. LABEL BREAKERS SERVICING SPACES AS "SPARE". VERIFY NO OTHER DEVICES REMAINING IN SERVICE ARE CONNECTED TO REMOVED CIRCUITS. IF SO, MAINTAIN CIRCUITS (1 - ED-112). ☐ Yes ☐ No

* REMOVE EXHAUST FANS, CONDUIT, WIRING, JUNCTION BOXES AND ASSOCIATED MATERIALS TO SOURCE. DISCARD ALL MATERIALS. LABEL BREAKERS SERVICING SPACES AS "SPARE". VERIFY NO OTHER DEVICES REMAINING IN SERVICE ARE CONNECTED TO REMOVED CIRCUITS. IF SO, MAINTAIN CIRCUITS (1 - ED-113). ☐ Yes ☐ No

* REMOVE EXTERIOR SWITCH AND RETAIN FOR RELOCATION (2 - ED-113). ☐ Yes ☐ No

Mechanical Demolition (Per Mechanical Demolition Plans (MHD-104, MPD-204, & MD-105.1)):

* Mechanical Demolition as shown on MHD-104. ☐ Yes ☐ No

* Mechanical Piping Demolition as shown on MPD-204. ☐ Yes ☐ No

* Mechanical Ductwork Demolition as shown on MD-105.1. ☐ Yes ☐ No

Plumbing Demolition (Per Plumbing Demolition Plans (PD-110 & PD111)):

* REMOVE WASTE PIPING TO THIS INDICATED LOCATION (1 - PD-110). ☐ Yes ☐ No

* COORDINATE OVERHEAD WORK WITH OWNER PRIOR TO CONSTRUCTION. DEMOLITION WILL AFFECT OPERATING ROOM OPERATIONS (2 - PD-110). ☐ Yes ☐ No

* REMOVE EXISTING 2"V TO THIS POINT (1 - PD-111). ☐ Yes ☐ No

* REMOVE EXISTING 2 1/2"CW AND 1 1/2"HW TO THIS POINT (2 - PD-111). ☐ Yes ☐ No

* REMOVE EXISTING 2"RO PIPING TO THIS POINT (3 - PD-111). ☐ Yes ☐ No

* REMOVE EXISTING PLUMBING FIXTURE, MIXING VALVE, EYEWASH AND ALL RELATED PIPING SERVING THE FIXTURE (4 - PD-111). ☐ Yes ☐ No

* REMOVE EXISTING EMERGENCY SHOWER, MIXING VALVE AND ALL RELATED PIPING. REMOVE FLOOR DRAIN AND PATCH FLOOR AS REQUIRED (5 - PD-111). ☐ Yes ☐ No

* REMOVE EXISTING PLUMBING FIXTURE, MIXING VALVE, EYEWASH, RO PIPING AND ALL RELATED PLUMBING PIPING SERVING THE FIXTURE (6 - PD-111). ☐ Yes ☐ No

* REMOVE ALL PLUMBING PIPING, INCLUDING RO, IN UTILITY CHASE TO FIXTURES AND EQUIPMENT ON WORK STATIONS (7 - PD-111). ☐ Yes ☐ No

* REMOVE RO PIPING AND PLUMBING PIPING, IN WALL AS INDICATED (8 - PD-111). ☐ Yes ☐ No

* PROVIDE TEMPORARY 2" DI LOOP CONNECTION DURING CONSTRUCTION. COORDINATE OUTAGE WITH OWNER (9 - PD-111). ☐ Yes ☐ No

Technology Demolition (Per Technology Demolition Plan (T-101)):

* EXISTING WIRELESS ACCESS POINTS TO BE REMOVED AND RELOCATED TO NEW LOCATION DURING RENOVATION. SEE TECHNOLOGY PLAN FOR MORE DETAILS (T-101) ☐ Yes ☐ No

Scope-Specific Clarifications**Specific Exclusions:**

Asbestos Abatement

NO NEW CORES ARE PERMITTED THROUGH EXISTING CONCRETE BEAMS OR COLUMNS. IF REQUIRED, CORES SHOULD ONLY BE DRILLED THROUGH THE EXISTING SLAB.

Structural Demo from Sheets SD200 & SD250.

26-0024: UTSW CUH 4.219 Microbiology Lab

6201 Harry Hines Boulevard, Dallas, TX 75235, United States of America

General Acknowledgments

Mark "yes" to all yes/no questions »

GENERAL INFECTION CONTROL NOTES:

- * Maintain/meet a Class IV infection control classification. ☐ Yes ☐ No
- * A. OBTAIN FROM THE OWNER A COPY OF THE INFECTION CONTROL RISK ASSESSMENT (ICRA) PREPARED FOR THIS PROJECT. REVIEW THE REQUIREMENTS IN THE REPORT AND PERFORM ALL WORK IN ACCORDANCE WITH THOSE PROTOCOLS. STRICTLY ADHERE TO THE LIMITS OF THE CONSTRUCTION AREA, AND WHERE PHASING APPLIES, ADHERE TO PHASING PLAN. COORDINATE ANY WORK OUTSIDE THE CONSTRUCTION AREA WITH THE OWNER AND PERFORM IT IN ACCORDANCE WITH THE ICRA REPORT, UNDER THE SUPERVISION OF THE OWNER'S REPRESENTATIVE OR OTHER DESIGNATED ICRA COMMITTEE OFFICER. ☐ Yes ☐ No
- * B. TO THE EXTENT THAT IS REQUIRED BY THE ICRA, ENDEAVOR TO MAINTAIN EXISTING LEVELS OF INDOOR AIR QUALITY IN AREAS SURROUNDING AND ADJACENT TO THE CONSTRUCTION WORK ZONE, AND ELSEWHERE IN THE FACILITY. IT SHOULD BE ANTICIPATED THAT THE ICRA REPORT WILL REQUIRE MEASURES TO THIS EFFECT, INCLUDING THE ASSEMBLY OF THE CONSTRUCTION ZONE BARRIERS. ☐ Yes ☐ No
- * C. PERFORM CONSTRUCTION ACTIVITIES IN AREAS THAT ARE OCCUPIED BY THE HOSPITAL STAFF, THE GENERAL PUBLIC, OR HOSPITAL PATIENTS PER THE REQUIREMENTS OF THE OWNER'S ICRA. WHERE CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED, RETURN THE AREA TO "CLEAN" CONDITIONS, AS DEFINED BY THE OWNER'S PROTOCOLS, BEFORE IT IS OCCUPIED BY THE HOSPITAL STAFF, THE GENERAL PUBLIC, OR HOSPITAL PATIENTS. ☐ Yes ☐ No

Work Hours & Restrictions:

On-Site Work Hours:

- * Owner's Special Conditions set normal hours at 7:00 AM–5:00 PM; after hours 6:00 PM–6:00 AM; weekends permitted. Work generating excessive noise, odor, or vibration, and any work above the active Level 3 operating rooms, must be performed after hours or on weekends (Owner has confirmed all work above active ORs is overtime/night work). Flooring scope is on Level 4 inside the contained renovation area, so we anticipate straight time – but carry the flexibility, and note the GC is responsible for OT/weekend work needed to hold schedule. ☐ Yes ☐ No

Work Restrictions:

- * THE BUILDING WILL BE OCCUPIED DURING CONSTRUCTION. COORDINATE WITH OWNER ON SCHEDULING CONSTRUCTION OPERATIONS THAT GENERATE VIBRATION, NOISE, SECURITY CONCERNS, POWER INTERRUPTIONS, SMELLS OR OTHER CONSTRUCTION ACTIVITIES THAT MAY DISRUPT OPERATION IN ADJACENT SPACES. ☐ Yes ☐ No
- * Comply with limitations on use of public streets and other requirements of authorities having jurisdiction. ☐ Yes ☐ No

Jobsite Access:

- * This is a renovation inside Clements University Hospital with active clinical space adjacent and below. ICRA/infection control applies: negative air machines with HEPA at all times, hard-panel containment barriers, tacky and walk-off mats, covered trash buggies with wheels cleaned entering/leaving, daily debris removal. All personnel need UTSW badges and current UTSW safety training. No free parking – UTSW parking policy applies. ☐ Yes ☐ No

Parking:

- * No free parking. Parking is as per UTSW parking policy. ☐ Yes ☐ No

Employee Identification:

Addendum Acknowledgment:

- * Addendum 1 ☐ Yes ☐ No
- * Addendum 2 ☐ Yes ☐ No
- * Addendum 3 ☐ Yes ☐ No
- * Addendum 4 ☐ Yes ☐ No
- * Addendum 5 ☐ Yes ☐ No
- * Addendum 6 ☐ Yes ☐ No
- * Addendum 7 ☐ Yes ☐ No
- * Addendum 8 ☐ Yes ☐ No

26-0024: UTSW CUH 4.219 Microbiology Lab

6201 Harry Hines Boulevard, Dallas, TX 75235, United States of America

* Addendum 9

☐ Yes ☐ No**Q&A Acknowledgement:**

* Q&A Dated 08-26-2026

☐ Yes ☐ No**Taxes:**

* Sales Tax on Materials Included?

☐ Yes ☐ No

* Cost Breakout of Sales Tax on Materials ==> ENTER DOLLAR VALUE \$

\$

Lead Times:

* Shop Drawing / Submittal Lead Time

input response here

* Product Lead Time Description(s) & # of Weeks

input response here

Labor Rates:

* Wage Rates per project requirements (i.e., Prevailing Wage, Davis Bacon, etc. As Applicable)

☐ Yes ☐ No

The undersigned acknowledges that material substitutions are not permitted unless expressly approved in writing by Arch/Eng through Requests for substitutions must include detailed specifications and documentation for review and approval prior to bid submission:

Please acknowledge that you have read and agree with the information, procedures, and requirements listed in the following Specifications & Documents:

00 - RFP:

* RFP_Sealed_Proposal_-_CUH_3T_MRI_WITH_HIFU_AND_TULSA

☐ Yes ☐ No**01 - Plans:**

* Campus Map

☐ Yes ☐ No

* IFC Drawings 07.28.2026

☐ Yes ☐ No**02 - Specifications:**

* UTSW-CUH-MRI 4 IFC PROJECT MANUAL

☐ Yes ☐ No**03 - Addenda:****04 - Owner's Special Conditions:**

* Owner's Special Conditions

☐ Yes ☐ No**05 - Safety & Security:**

* Construction Site Safety Manual FY22

☐ Yes ☐ No

* Environmental of Care Fire & Life Safety Policy

☐ Yes ☐ No

* Project Safety Requirements

☐ Yes ☐ No**06 - Planning & Scheduling:**

* Project Planning and Scheduling

☐ Yes ☐ No**07 - UTSW Uniform Specs & Acknowledgements:**

* Project Quality Control

☐ Yes ☐ No

* UGCs

☐ Yes ☐ No**08 - Wage Rates:**

* Wage Determination

☐ Yes ☐ No**09 - Q&A Clarifications:****10 - Additional Information:**

26-0024: UTSW CUH 4.219 Microbiology Lab
6201 Harry Hines Boulevard, Dallas, TX 75235, United States of America

* Change Order Form CSP	☐ Yes	☐ No
* CUH Asbestos Free Letter	☐ Yes	☐ No
* General Commissioning Requirements	☐ Yes	☐ No
* Project Administration Templates	☐ Yes	☐ No
* Project Closeout Procedures	☐ Yes	☐ No
* utsw design guidelines vol 1 ada	☐ Yes	☐ No
* utsw design guidelines vol 2 ada	☐ Yes	☐ No
* utsw design guidelines vol 3 ada	☐ Yes	☐ No
* UTSW_VETHUB_SP_v2	☐ Yes	☐ No

Bond Information

* Payment & Performance Bond Add (If Required) % Percentage	OR		%
* Payment & Performance Bond Add (If Required) Dollar Amount		\$	

Certifications

* Certified VetHUB? (Project goal of 1%)	☐ Yes	☐ No
* Participation Included in Base Bid (% of VetHUB subcontractor total base bid)	input response here	
* Certification Agency	input response here	
* Certification Number	input response here	

Attachments